WASHINGTON - DULLES INTERNATIONAL AIRPORT MAIN TERMINAL INTERNATIONAL ARRIVALS BUILDING





OWNER:

METROPOLITAN WASHINGTON AIRPORTS AUTHORITY

OWNER'S REPRESENTATIVE:

RICHARD TURNER PROJECT MANAGER METROPOLITAN WASHINGTON AIRPORT AUTHORITY (MWAA)

BNP PROJECT MANAGER:

NICK TRIANTAFILIDIS

LOCATION:

WASHINGTON, DC

COMPLETION DATE: 2011

OVERALL PROGRAM CONSTRUCTION AMOUNT:

US \$98 MILLION

REFERENCE:

METROPOLITAN WASHINGTON AIRPORT AUTHORITY (MWAA) 45045 AVIATION DRIVE SUITE 300 DULLES, VA 20166-7528 TELEPHONE: (703) 572-0285

SCOPE OF SERVICES:

CONCEPTUAL DESIGN
DESIGN DEVELOPMENT
CONTRACT DOCUMENTS
BIDDING AND PROCUREMENT
CONSTRUCTION MONITORING

BNP was retained by the Metropolitan Washington Airports Authority as part of the Pierce Goodwin Alexander & Linville (PGAL) Architectural/Engineering Design Team for the facility planning, design and construction of the Main Terminal International Arrivals Building.

The expansion of the International Arrivals Building and associated inbound Baggage Handling System, which was considered one of the Authority's major upgrades and improvements program for the Main Terminal, was designed to address deficiencies in the size and configuration of the existing facility spaces and to increase passenger-processing capacity to accommodate the forecasted flight schedule.

The overall program included six new inclined plate claim devices, totaling 1772 linear feet of passenger presentation. Each claim device is fed from its respective dual-feed conveyor lines, which are located at the basement level bagroom space. The inbound operation also includes a 60" wide Oddsize conveyor line for oversize baggage items.

Initially the inbound operation at the basement level was divided between two separate bagrooms, which was later consolidated into one to clear the right-of-way for a new outbound Checked Baggage Inspection System, at the west end of the Main Terminal. The layout of the proposed Arrivals Level Claim Hall and associated bagroom operation was studied between the PGAL design team disciplines through a number of alternate concepts, to evaluate the proposed claim device requirements and their relation or influence to the necessary space capacity requirements, passenger flows and exit control, and evolved through detail design and construction documents.

The construction program was performed utilizing a phased-in implementation process that was divided into three major phases to minimize disruption to passengers and airline operations. The first phase expanded the Arrivals Hall and Primary Inspection Area, the seconde phase expanded the baggage Claim Hall and the third phase replaced the original baggage Claim Hall.

